OFFICE OF THE SUPERINTENDING ENGINEER, IRRIGATION CIRCLE, K. R. S. WORKS, MYSORE.

Notification No. 9734, *dated 9th May* 1939.

Applications are invited from candidates who are Graduates in Engineering (Civil) ,for appointment as Work Inspectors on Rs. 50 per mensem for the subordintae supervision of the Cauvery and Shimsha Branch Works.

2. The appointments are purely temporary, borne on the Work Establishment of the Division, and terminable without notice.

3. The applications should be in the form prescribed by the Central Recruitment Board, and should reach the undersigned on or before 3rd June 1939.

4. The appointments are open to candidates of all communities.

N. SARABHOJA,
Superintending Engineer.

ENGINEERING DEPARTMENT.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 15*th May* 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 26th May 1939, for providing flushing system to latrines and underground drainage arrangement to New Police Lines at Mysore Road, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by 15th June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 492 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for providing flushing system to latrines and underground drainage arrangement to New Police Lines at Mysore Road, Bangalore City," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities for the work of providing flushing system to latrines and underground drainage arrangement to New Police Lines at Mysore Road, Bangalore City.

No.	Items of work	Unit	Quantity
1	Providing 7″ S.W. pipe laying and jointing in cement 1 : 2 earthwork excavation of hard and soft soil and removing boulders and cutting hard and soft rock, refilling, watering and tamping by 1 ft. each layer and testing with water and removing surplus earth and carting rock, boulders, etc., and cost of barricading and lighting complete ..	R.ft.	950
2	Do do 6″ S.W. pipe as per above	,,	448
3	Do do 4″ up to bottom of the manhole, etc., as per above	,,	1,024

No.	Items of work	Unit	Quantity
4	Constructing manhole 3' Dia. inside up to 3' depth and 4' diar. for more with 9" cement concrete (1 : 2½ : 5) bed and 9" brick in cement mortar and ½" cement plastering 1 : 2 and earthwork excavation and cutting hard and soft rock and removing boulders and carting surplus earth, boulders, rock and barricading and lighting and making drains, etc., complete and providing 2 Cwts. manhole cover and frame and C.I. steps	No.	10
5	Do over 3 feet up to 6 feet depth	,,	12
6	Do over 6 and 7 and 8 feet depth above 6 feet 1⅛' wall and 1' concrete bed, etc., as per above	,,	4
7	Boring hole in existing municipal main and re-doing the same with cement mortar, constructing drain and cement plastering complete..	,,	1
8	Tarring Road	S.ft.	50
9	Constructing ventilating shaft by providing 20 ft. length 4" dia. boiler tube pipes 4" bends and 4" cowls, etc., including constructing 2 feet height masonry support and cement plastering, etc., complete ..	No.	4
10	Road crossing with new metal and gravel, etc., complete	,,	200
11	Dismantling conservancy latrine seat and removing platform and earthwork excavation and removing rubbish and filling concrete complete and making slope towards the close and cement plastering with red ochre	,,	60
12	Providing and fixing 4" circular mouthed stoneware trap, including fixing in cement concrete all round and bottom, etc., complete	,,	60
13	Providing cement concrete closet pan with expanded metal and cement plastering inside and providing foot rest complete	,,	60
14	Constructing open channel cement concrete drain to connecting the cement pan from existing drain and providing and fixing C.I. grating, etc., complete	,,	60
15	Stone wall bore and redoing the same with cement and cement pointing.	,,	60
16	Dismantling and reconstructing big stone masonry 3 feet width open drain and removing burnt stone slab and refixing the same, etc., complete	,,	1

N. KRISHNIENGAR,
Sanitary Engineer.

Printed by the Superintendent at the Government Press, Bangalore.